

**In the specification**

*Please amend paragraph 27 as follows:*

[0027] A method of pre-assembling an electrical fuse relay box 100 is illustrated in the flow diagram shown in Figure 4. The method comprises mounting a plurality of electrical components within the upper compartment 75 of the frame 5 of the fuse box 100 at step 200. Second, a plurality of connector modules 6 are mounted within the lower compartment 76 of the frame 5 of the fuse box 100 at step[[p]] 210, wherein the connector modules 6 are configured for electrically engaging electrical wires, and wherein the connector modules 6 comprise connection contacts 15. Next, an upper cover 7 is positioned on the upper compartment 75 of the frame 5 at step 220. Then, a lower cover is positioned on the lower compartment 76 of the frame 5 at step 230. Finally, connection contacts 15 are extended through the frame 5 to make an electrical connection with the electrical components 20 at step 240.